

Melbourne's Grade Separation Programme- Minimising Operational Disruption

Jamie Green – Major Projects Executive



30 November 2016

CONTENTS

1. Melbourne's Grade Separation Challenge
2. Three steps to minimising disruption
3. Step 1 - Procurement
4. Step 2 - Grade Separation Types
5. Grade 3 - Grade Separation Construction
6. Focus on Caulfield to Dandenong Project
7. Key Messages
8. Questions



MELBOURNE'S CHALLENGE



- 50 level crossings
- Assume 2 weeks rail closure per level crossing
- 16 months rail closure + much greater disruption

GRADE SEPARATIONS – MINIMISING DISRUPTION


Three steps:-

- 1) Sticking plaster approach - package grade separations on a line
- 2) Aim for a minimum disruption option
- 3) Minimise construction impacts



STEP 1 - GRADE SEPARATION PACKAGING

- Traditionally grade separations delivered singly
- Several weeks rail closure disruption
- Typically \$100-150m
- Unsustainable delivery
- Level Crossing Removal Authority created
- Crossings packaged by line/area



STEP 2 - MINIMAL DISRUPTION REMOVAL OPTION

Description	Melbourne Examples
Road closure	New Street, Brighton
Road Over	Warragul Road, Oakleigh North Road, Huntingdale
Road Under	Anderson Road North, Sunshine
Rail Over	Glenferrie Road, Hawthorn
Rail Under	Springvale Road, Springvale Centre Road, Bentleigh



Increased
rail
disruption



Increased
rail
disruption



Description	Melbourne Examples
Offline	Springvale Road, Springvale
Temporary Slew	Anderson Road South, Sunshine
Online	Centre Road, Bentleigh

ROAD OVER



North Road,
Huntingdale



Warragul Road,
Oakleigh

ROAD UNDER



Anderson Road North,
Sunshine




Victoria Street, Middle
Footscray

RAIL OVER



Glenferrie Road,
Hawthorn



Carlisle Street,
Balaclava



Nepean H'wy,
Elsternwick



Flinders Street Viaduct



North Road,
Brighton



Nightingale St, St Kilda
East

RAIL UNDER



Rooks Road,
Mitcham




Centre Road,
Bentleigh



Springvale Road,
Springvale


GRADE SEPARATION TIMELINE FOR METROPOLITAN MELBOURNE



Taken from “*The Benefits of Level Crossing Removals - Lessons from Melbourne's historical experience*” by RMIT.

STEP 3 – CONSTRUCTION METHODS

CAULFIELD TO DANDENONG (CTD) OVERVIEW



CTD HORIZONTAL AND VERTICAL ALIGNMENT SOLUTION

Area	Level Crossing	Crossing Type	Construction Type
1	Grange Road	Elevated rail over	Offline to south
	Koornang Road	Elevated rail over	Offline to north and south
	Murrumbeena Road	Elevated rail over	Offline to north and south
	Poath Road	Elevated rail over	Offline to north and south
2	Clayton Road	Elevated rail over	Offline to the north
	Centre Road	Elevated rail over	Offline to the north
3	Corrigan Road	Elevated rail over	Offline to the north
	Heatherton Road	Elevated rail over	Offline to the north
	Chandler Road	Elevated rail over	Offline to the south

9 Over

9 Offline




4 Viaduct structures




RAIL SYSTEMS ON VIADUCT


- Integrated rail solution
- Vosloh integrated fixed track system
- LED tilt mast signals
- No location cases on viaduct, SERs are on stations, REBs/loc's on ground under the viaduct
- Architecturally designed OHW masts
- Integrated CSR





3D MODEL USED FOR SIGNAL SIGHTING



TILT SIGNALS




AREA 1 - CREATING A SAFE / OFFLINE CONSTRUCTION ZONE



- Very narrow 20m rail corridor
- Install barriers – create safe zone
- Work in area between barriers and rail boundary – 5 to 6m working room

AREA 1 – MINIMIZING DISRUPTION




- Piles and pile caps cast in situ behind hoarding
- Bridge piers and deck are precast
- 90% of viaduct construction completed offline with no impact to train services

AREA 1 – CARRIER CONSTRUCTION METHOD



CTD CONSTRUCTION – AREA'S 2 AND 3



- Similar to Area 1 – rail safety, offline construction, precast
- Access easier from adjacent local roads
- Access allows Super-T construction – highly efficient

CTD CONSTRUCTION IMPACT

9 level crossings removed using:-

- 24 Weekend occos
- 1 x 8 day occo
- 2 x 16 day occos

90% of all construction offline.

Note: Occupations for level crossing removals only. Additional occos required for wider CPLU works.



KEY MESSAGES



Step 1 - Work packaging



No 'one size fits all' solution



Step 2 - Aim for minimal railway intervention solution



Step 3 - Innovative construction

Questions?